

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Z - 5
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin, deputy, on October 24, 1871, under GLO contract No. 154, as follows:

Set a stone, 20" x 7" x 5", for corner to sections 5, 6, 31 and 32.

T1S R30E
S31|S32
S6|S5
PLS 1636
T2S
2004

Original corner evidence recovered:

Found the original corner stone solidly set 12" into the ground on the east edge of a mound of stones. The original corner stone is 20" x 7" x 6" and is plainly marked with five notches on the east edge

Monument and accessories established to perpetuate the original position of this corner:

In place of the corner stone, I set a 1" x 30" flared, galvanized iron pipe 25" into the ground. I bury the corner stone along the south side of the pipe and build a mound of stones around the pipe. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above, from which:

- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 32", attached at ground level, bears N47° E, 109.0 feet.
- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S5", attached at ground level, bears S42° 30' E, 118.0 feet.
- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S6", attached at ground level, bears S48° W, 127.5 feet.
- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 31", attached at ground level, bears N52° W, 113.3 feet.

I hereby certify the above corner point was perpetuated as hereon described on February 9, 2004. Magnetic declination set in compass: 16 ° E.
NAD '83 UTM Zone 11 position: 5032838N, 333742E (plus or minus two meters).

Dennis L. Gaylord

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

OREGON
JULY 14, 1978
DENNIS L. GAYLORD
1636
Renews June 30, 2005

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on:

RECEIVED BY
Umatilla County Surveyor
Date 2-04
Rec'd By KK
No. 04-34-R