

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Index: R-13

Corner, Secs. 21, 22, 27, & 28, T1S, R32E, WM.

Corner originally set by Daniel Chaplin in contract 107 dated Sept, 21, 1864, his record reads:
Set post for Cor. to secs 15, 16, 21, and 22, in mound of earth with charred stake, pits, trench, etc. as per instructions.

DIAGRAM

T1S	R32E
S21	S22

S28	S27
1995	
PLS 852	

Description of corner evidence found:
None

Description of monument and accessories I established to perpetuate the original location of this corner:

The corner is at the corner of a fence with fences running North and West. This fence corner was called acceptable and used as the corner in surveys Q-863-B and 92-88-B by PLS 346. I set a 1 1/2"x30" galvanized iron pipe with a 2 1/2" Brass cap stamped as in the diagram above 5' west of the true corner location on line for a witness monument. The witness monument and the bearing objects are all recorded in reference to the true corner location.

- A 5/8"x24" rebar with 2" Al cap bears N02°25'E, 29.9', stamped B.O., ORLS 852, AND WALS 13922.
- A 5/8"x24" rebar with 2" Al cap bears N45°13'W, 14.9', stamped B.O., ORLS 852, AND WALS 13922.
- A 5/8"x24" rebar with 2" Al cap bears S33°52'E, 1.5', stamped B.O., ORLS 852, AND WALS 13922.
- A 5/8"x24" rebar with 2" Al cap bears S89°15'W, 30.0', stamped B.O., ORLS 852, AND WALS 13922.

The bearings are based on the section line to the north being N 00°28' 33" E.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

David L. Haddock

OREGON
JULY 12, 1968
DAVID L. HADDOCK
852

This work was done Septmber 27, 1995 and witnessed by Stephen Haddock.

Office of Umatilla Survey Dept. County of Umatilla
State of OREGON, I hereby certify that the within instrument was filed
in this office for record on the 23rd day of October, 1995.

(COUNTY OFFICIAL)

by

(DEPUTY)

RECEIVED BY

Umatilla County Surveyor
Date 10-95
Rec'd By KE
No. 95-187-R