

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 10/4/94

CORNER DESIGNATION: A-17. Northeast corner Section 3, T1S., R34E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Most recent approved GLO Survey was made by James P. Currin and James Noland, under Special Contract dated May 4, 1887. Notes state: "Set basalt stone, 20 x 12 x 4 ins., 15 ins. in ground for Closing Cor. to Secs. 2 & 3, marked CC. with 4 notches on W. and 2 notches on E. edges. Raised mound of stone around it."

MONUMENT AND ACCESSORIES FOUND: None. Corner re-established using single proportionate measurement between the recovered Southeast corner Section 34 and the recovered Southwest corner Section 35, T 1 N., R 34 E., using James P. Currin and James Noland record under GLO Contract dated May 4, 1887.

MONUMENT MARKING DETAIL:

T1N R34E
 CC

 S3 | S2
 T1S R34E
 1994
 PLS 1106

MONUMENT SET: At position determined by survey, set a 2 1/2" brass cap on a 1 1/4" x 30" galvanized iron pipe, 12" in the ground, with mound of stone to cap, (marked as shown in the monument detail).

New Accessories:

Set steel fence post 2.5 feet North of monument, with witness sign attached.
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106" bears S 14° W-22.8 feet.
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106" bears S 03 1/2° W-13.3 feet.
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106" bears S 44° E-27.5 feet.
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106" bears S 55° E-23.3 feet.
Attached bearing object signs to pins. Set steel fence post with witness sign attached near each iron pin.

LOCATION & COMMENTS:

STATE PLANE CO-ORDINATE:

Oregon North Zone, NAD 83/91, U.S. Survey Foot:
N = 680087.86
E = 8707096.79

COMPASS DECLINATION: 18° East.

Surveyor's Seal

FIRM/AGENCY: William R. Wells, PLS
P.O. Box 1696
Pendleton, Oregon 97801

Party Chief: Robert D. English
Notes: Robert D. English
Witness: F. Scot Munro

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6/30/96

RECEIVED BY
Umatilla County Surveyor
Date 2-95
Rec'd By RR
No. 95-16-C