

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla      DATE: 10/4/94

CORNER DESIGNATION: A-5. Northeast corner Section 6, T1S., R34E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Most recent approved GLO Survey was made by James P. Currin and James Noland, under Special Contract dated May 4, 1887. Notes state: "Set post, 48 x 4 x 4 ins., 2 ft. in ground for Closing Cor. to Secs. 5 & 6, marked, T.1 S., R. 34 E., S.5 on S.E. S.6 on S.W., T.1N., R.34 E., S.32 on N., C.C. on S. with 5 notches on E. edge, 1 notch on W. edge, from which, A pine, 14 ins. diam. brs. S.42°E., 63 lks. dist., marked T.1S., R.34 E., S.5, B.T. A pine, 6 ins. diam., brs. S.70°W., 23 lks. dist., marked T.1 S., R.34 E., S.6, B.T. A pine, 6 ins. diam., brs. N.45°W., 59 lks. dist., marked T.1 N., R.34 E., S. 32, B.T."

MONUMENT AND ACCESSORIES FOUND: None. Corner re-established using single proportionate measurement between the re-established South 1/4 corner Section 31 and the recovered South 1/4 corner Section 33, using James P. Currin and James Noland record under GLO Contract dated May 4, 1887.

**MONUMENT MARKING DETAIL:**

T1N            R34E  
                  CC  
                  -----  
                  S6 | S5  
                  T1S R34E  
                  1994  
                  PLS 1106

MONUMENT SET: At position determined by survey set a 2 1/2" brass cap on a 1 1/4" x 30" galvanized iron pipe, 28" in the ground, with mound of stone to cap, (marked as shown in the monument detail).

**New Accessories:**

Set steel fence post 1.7 feet North of monument, with witness sign attached.

A 16" ponderosa pine bears S 58° E-110.0 feet, scribed: T1S R34E S5 CC BT.

An 18" douglas fir bears S 40° E-55.0 feet, scribed: T1S R34E S5 CC BT.

A 13" ponderosa pine bears S 10° W-49.5 feet, scribed: T1S R34E S6 CC BT.

A 12" douglas fir bears S 47 1/2° W-31.8 feet, scribed: T1S R34E S6 CC BT.

Bearing trees have a brass washer stamped 'PLS 1106' nailed to the face of the blaze. Attached bearing object and witness signs to each tree; painted a 6" band and face of blaze red.

LOCATION & COMMENTS: Corner is on South edge of skid trail cut into hillside.

**STATE PLANE CO-ORDINATE:**

Oregon North Zone, NAD 83/91, U.S. Survey Foot:

N = 679688.67

E = 8691223.25

RECEIVED BY

Umatilla County Surveyor

Date 2-95

Rec'd By KK

No. 95-16-C

COMPASS DECLINATION: 18° East.

Surveyor's Seal

FIRM/AGENCY: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, Oregon 97801

Party Chief: Robert D. English  
Notes: Robert D. English  
Witness: F. Scot Munro

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*Renews 6/30/96*

RECEIVED BY

Umatilla County Surveyor

Date 2-95

Rec'd By KK

No. 95-16-C