

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 9/19/94

CORNER DESIGNATION: A-9. Northeast corner Section 5, T1S., R34E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Most recent approved GLO Survey was made by James P. Currin and James Noland, under Special Contract dated May 4, 1887. Notes state: "Set basalt stone, 16 x 16 x 16 ins., 10 ins. on ground, for Closing Cor. to Secs. 4 & 5, marked CC. with 4 notches on E. and 2 notches on W. edges. Raised mound of stone around it."

MONUMENT AND ACCESSORIES FOUND: Found 17" x 12" x 12" basalt stone in undisturbed condition with markings "X" on top, "CC" and notches on side.

MONUMENT MARKING DETAIL:

T1N R34E
CC

S5 | S4
T1S R34E
1994
PLS 1106

MONUMENT SET: At position of found original stone, set a 2 1/2" brass cap on a 1" x 30" galvanized iron pipe, 14" in the ground, with mound of stone to cap, (marked as shown in the monument detail).

New Accessories:

Set steel fence post 1.7 feet North of monument, with witness sign attached.
A brass washer stamped 'PLS 1106' at corner post rock jack, bears S 77° E-9.5 feet.
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears S 28° E-20.1 feet.
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears S 14° W-29.0 feet.
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears S 57° W-24.2 feet.
Attached bearing object sign to each pin. Set steel fence post with witness sign attached near each pin.
Nailed witness sign above brass washer on corner post.

LOCATION & COMMENTS:

Corner located 10' west of fence corner with fences going East and South.

STATE PLANE CO-ORDINATE:

Oregon North Zone, NAD 83/91, U.S. Survey Foot:
N = 679812.90
E = 8696484.94

COMPASS DECLINATION: 18° East.

Surveyor's Seal

FIRM/AGENCY: William R. Wells, PLS
P.O. Box 1696
Pendleton, Oregon 97801

Party Chief: Robert D. English
Notes: Robert D. English
Witness: F. Scot Munro

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6/30/96

RECEIVED BY

Umatilla County Surveyor

Date 2-95

Rec'd By KK

No. 95-16-C