

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 09/26/08.

CORNER DESIGNATION: J-21, The Southeast Corner of Section 11, Township 1 South, Range 34 East, W.M..

PREVIOUS RENEWALS/SURVEYS ETC: Corner originally established by James P. Currin and James E. Noland under their Special Contract dated May 4th, 1887. Notes state: Set basalt stone 20 x 10 x 10, 15 ins. in the ground, marked 4 notches on S., 1 notch on East edges, for corner to sections 11, 12, 13, and 14, and raised a mound of stone around it.

MONUMENT AND ACCESSORIES FOUND: Found 18"x10"x10" stone in center of mound of 3 1/2 foot stone with a old "K" tag on ponderosa pine tree 19 feet Southeast of corner. No marks were observed on the stone. Portions of the stone have broken off.

MONUMENT MARKING DETAIL:

T1S R34E
S11|S12
S14|S13
2008
PLS 1106

MONUMENT SET: At the center of found corner stone set a 5/8"x24" iron rebar with a 2" aluminum cap 21" inches in the ground. Placed original stone on the East side of the monument, and surrounded new monument with stone and earth. Cap is marked as shown in "Monument Marking Detail".

New accessories:

- A 6" ponderosa pine scribed "T1SR34ES12BT" on single blaze bears North 78° East, 60.2 feet.
- A 8" ponderosa pine scribed "T1SR34ES13BT" on single blaze bears South 74° East, 85.7 feet.
- A 18" ponderosa pine scribed "T1SR34ES14BT" on single blaze bears South 21° West, 46.6 feet.
- A 6" ponderosa pine scribed "X" at breast height and "BT" at base bears North 57° West, 25.3 feet.

Attached bearing tree signs to all new bearing trees. Attached witness sign to a 21" ponderosa pine with old "K" tag 19 feet Southeast of corner.

LOCATION AND COMMENTS: Corner is located on flat ridge near the break of a steep South sloping hillside and approximately 19 feet North of a East-West fence. Approximately 50 feet West of corner, the fence line extends West.

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

\1S34J21

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6-30-10

RECEIVED BY

Umatilla County Surveyor

Date 10-08

Rec'd By KK

No. 08-132-R