

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

J-25

History of original corner establishment:


Original survey by Currin and Noland under their special contract, 1887:

Set a Basalt Stone 9x8x7 ins. 6 ins. in the ground for corner to Sec's 7,12,13 and 18 marked 4 notches on S and 2 on N edges from which:

A Pine 12 ins. in diam. bears N 25°W 61 lks. dist., marked T1S R34E S12 BT.

A Pine 12 ins. in diam. bears S 72° E 163 lks. dist. marked T1S R35E S18 BT. No other trees in limits. Raised mound of stone alongside.

NOTE: Subdivisions of T1S R35E by Currin, Et Al, 1887 established closing corners on the line between Ranges 34 and 35 East for the survey lines in T1S R35E.



Description of corner evidence found:

Found a Basalt stone 12"x7"x7" with 4 faint notches on an edge and 2 grooves on an opposite, narrow face, lying loose in a mound of stone approx 2' diameter and 1 ft. high.

The original SE bearing tree, a rotted stump flush in ground with tree lying alongside, rotted, approx. 16" diam, scribing "T1S R35E BT" plainly visible on previously opened double blaze.

No evidence remains for original NW bearing tree.

Description of monument and accessories established to perpetuate the original location of this corner:

At the corner point established alongside the found stone mound and at the record bearing and distance to the remains of the original SE bearing tree, we set a 2"x30" galvanized iron pipe 20" in the ground to bedrock and in a mound of stone 2 1/2' dia. and 1 ft. high with brass cap attached, marked:

Bury original corner stone alongside,  
From which:

The original SE bearing tree as previously described bears S 72°E 107.6 ft.


We mark new bearing trees as follows:

A 15" Ponderosa Pine, scribed "T1S R34E S12 BT" on a double blaze bears N 28°W 57.7 ft.

and a 6" Douglas Fir, scribed "T1S R34E S13 BT" on a double blaze bears S32°W 85.2 ft.

Attached brass washer marked "LS 1099" to lower blaze of new BT's. Bearing and horizontal distance measured to the center of the bearing trees at ground level.

Staff Compass (19 1/2° East Declination) Steel Tape  
October 5, 1983 Witnesses: Gary Langlitz LS 1099  
Dick Humiston



Office of Surveyor County of Wasilla  
State of Oregon I hereby certify that the within instrument was filed in this office  
for record on the 11<sup>th</sup> day of November, 1983  
Daniel L. Humiston by Betty Cochran  
(COUNTY OFFICIAL) (DEPUTY)