

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 8/10/95

CORNER DESIGNATION: L-11. Center 1/4 corner Section 16, T1S., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner established in 1974, by Survey No. J-77.

MONUMENT AND ACCESSORIES FOUND: Found a 2 1/2" brass cap on a 2" galvanized iron pipe, protruding 8" out of mound of earth, marked as shown in monument marking detail.

MONUMENT MARKING DETAIL:

T1S R35E
C | C
Sec. 16
RLS 933
1974
RLS 933

MONUMENT SET:

New Accessories:

- A 13" western larch bears N 12° E, 7.3 feet, scribed "C 1/4 S 16 BT".
- A 12" douglas fir bears N 56° W, 24.7 feet, scribed "C 1/4 S 16 BT".
- A 14" douglas fir bears S 10° E, 28.6 feet, with a brass washer stamped "PLS 1106" nailed to West side of tree 9 ins. above ground.
- An 11" douglas fir bears S 63° W, 15.1 feet, with a brass washer stamped "PLS 1106" nailed to West side 9 ins. above ground.
- Set steel fence post 3 feet South of monument with witness sign attached.

LOCATION & COMMENTS:

COMPASS DECLINATION: 18° East.

Surveyor's Seal

FIRM/AGENCY: William R. Wells, PLS
P.O. Box 1696
Pendleton, Oregon 97801

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Party Chief: William R. Wells, PLS
Notes: Rodney Lewis, LSIT

William R. Wells
OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-96

RECEIVED BY

Umatilla County Surveyor

Date 10-95

Rec'd by KK

No. 95-168-B