


V-13

History of original corner establishment:

Corner originally established on October 7, 1882 by Rufus S. Moore under contract No. 451 as follows: set a properly marked post from which: A 3" Larch bears N20°E, 42 links (27.72 feet). A 3" Larch bears N16°W, 32 links (21.12 feet). A 3" Pine bears S73°W, 23 links (15.18 feet). A 12" Pine bears S18°E, 116 links (76.56 feet).



Manius Buchanan perpetuated the corner on June 28, 1895, under contract No. 635, as follows: Set a new post properly marked, from which: A 6" Larch bears N22°E, 17 links (11.22 feet). Moore's 12" Pine bears S18°E, 116 links (76.56 feet). A 5" Pine bears S46°30'W, 24 links (15.84 feet). A 5" Pine bears N74°W, 25 links (16.50 feet).

Description of corner evidence found:

A sawn Ponderosa Pine stump, now decayed, with a partly healed, charred lower blaze with fragmentary scribes visible bears S18°E, 76.6 feet.

A sawn Western Larch stump with a portion of a healed lower blaze bears N26°E, 11.2 feet.

A down and decayed Western Larch (record Pine) with full scribing visible which I recovered in 1981 is now gone, likely destroyed by recent logging operations. In 1981, I found the root hole of this tree to bear S46°30'W, 15.8 feet.

Description of monument and accessories I established to perpetuate the original location of this corner:

At the corner point as determined by record distance from the original bearing tree remnants, I set a 1" x 30" iron pipe 27" into the ground with a 2 1/2" brass cap attached. The cap is marked as shown in the diagram above. From which:

- A 9" White Fir bears S6°30'E, 65.7 feet scribed "T1S R35E S34 BT".
A 16" Western Larch bears S71°W, 62.6 feet scribed "T1S R35E S33 BT".
A 13" Western Larch bears N68°30'W, 97.9 feet scribed "T1S R35E S28 BT".
A 14" Western Larch bears N81°E, 94.9 feet scribed "T1S R35E S27 BT".

The new bearing trees have a 5/8" brass washer, marked "PLS 1636", nailed flush to the lower of double blazes. Each new bearing tree also has a "bearing tree" sign nailed above the blazes.

I hereby certify the above corner position was perpetuated as hereon described on August 5, 1995. Declination: 18°E.

REGISTERED PROFESSIONAL LAND SURVEYOR
Dennis L. Gaylord
OREGON JULY 14, 1978 DENNIS L. GAYLORD 1636
Renewed 6/30/1997

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....
(COUNTY OFFICIAL) by (DEPUTY)

RECEIVED BY
Wasilla County Surveyor
Date 10-95
Rec'd By KK
No. 95-162-R