

REPORT ON CONDITION OF FOUND GOVERNMENT CORNER X-25

Robert Butler

December 11, 1996


Umatilla County

Description of Corner as Set:

This corner was re-established by Andrew Blachly as part of an Oregon State Parks and Recreation Department Survey, CS #027-1992.

Monument Detail:

2½" diam. brass cap on 1½" diam. galvanized pipe left 0.3 ft. above ground.



T1S
R35E R36E
S36 ¼
1992
OSP-LS2168

New assessories:

Orange carsonite post 2.0' west of corner.

14" diam. spruce N 31° W 13.7' scribed "X Bt" with location poster.

11" diam. spruce S 70° W 5.2' scribed "X Bt." with location poster

15" diam. spruce S 27° W 15.0' scribed "T1S R35E ¼ S 36 Bt." with location poster

11" diam. spruce S 2° W 13.3' scribed "X Bt." with location poster.

Description of Corner Evidence Found:

Found 2½" diam. brass cap extending 2" above ground in good condition from which a:

14" spruce bears N 31° W, 13.7' marked "X Bt."

16" spruce bears S 27° W, 15.0' marked "T1S R35E ¼ S36 Bt."

11" spruce bears S2°W, 13.3' marked "X Bt."

12" spruce bears S70°W, 5.3' marked "X Bt."

T1S
R35E R36E
S36 ¼
1992
OSP-LS2168

RECEIVED BY
Umatilla County Surveyor
Date 12-96
Rec'd by RK
No. 98-194-B

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Robert E. Butler

OREGON
JULY 25, 1995
ROBERT E. BUTLER
2733

Expires 12/31/97
Oregon Dept. of Transportation
3012 Island Avenue
La Grande, OR 97850

X-25