


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

HISTORY OF ORIGINAL CORNER ESTABLISHED:

Not previously established.

T 1 S R 35 E Z-11



DESCRIPTION OF CORNER EVIDENCE FOUND:

None.

DESCRIPTION OF MONUMENT AND ACCESSORIES I ESTABLISHED TO MONUMENT THE LOCATION OF THIS CORNER:

At position determined by survey I set a 5/8" x 30" iron pin 29" in the ground, with 2 1/2" aluminum cap marked as shown below, surrounded by a rock slide, from which:

NEW BEARING OBJECTS:

- A 5" Douglas Fir bears South 5° East a dist. of 25.35 ft., marked X BT.
 - A 6" Douglas Fir bears North 76° West a dist. of 44.90 ft., marked 1/4 S33 BT.
 - A 7" Ponderosa Pine bears North 24° West a dist. of 35.45 ft., marked 1/4 S33 BT.
- No other trees in range.

Set steel fence post approx. 0.5 ft. West

Falls on steep South West face in old rock slide.

I hereby certify that the corner was monumented on July 9, 2019.

Witness: Kyle A. Tucker

REGISTERED
PROFESSIONAL
LAND SURVEYOR



OREGON
June 2, 2010
JEFFREY S. HSU
83571

Renewal Date: June 30, 2021

BAGETT GRIFFITH & BLACKMAN

T1S R35E
1/4
S33
T2S
2019
OPLS 83571

I used a steel tape and magnetic compass in the establishment of the new accessories. I used 13° East declination, the distances are to a 60d spike driven into the side of the root crown of the bearing trees. A brass washer marked OPLS 83571 is attached to the BT blaze of the new bearing trees.

Z-11

RECEIVED BY
Umatilla County Surveyor
Date: 12/5/22
Rec'd By: CT
No.: 22-135-R