

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 10/15/01

CORNER DESIGNATION: A-25, Township 1 South, Range 35 East, Section 1.

PREVIOUS RENEWALS/SURVEYS ETC.: U.S. Department of the Interior Dependent Resurvey of a Portion of the West Boundary, T1S, R36E., W.M., Oregon. Notes state: True point for the closing cor. of T. 1 S., Rs. 35 and 36 E. Set an iron post, 30 ins. long, 2 1/2 ins. diam., with magnetic, plastic breakaway base, 25 ins. in the ground, with brass cap (marked as shown in monument marking detail), from which

A Douglas fir, 10 ins. diam., bears S. 15 1/2° E., 30 lks. dist., mkd. T1S R36E S6 CC BT.

A Douglas fir, 19 ins. diam. bears S. 52° W., 44 lks. dist., mkd. T1S R35E S1 CC BT.

From this point, the original closing cor. of T. 1 S., Rs. 35 and 36 E., perpetuated and recorded by Douglas M. Ferguson, Registered Land Surveyor, No. 848, in 1972, bears N. 0° 31' E., 0.06 chs. dist., monumented with an iron post, 2 1/2 ins. diam., firmly set, projecting 6 ins. above ground, with brass cap mkd:

T 1 N 36 E S 31
S 1 | S 6
R 35 E | R 36 E
C C
T 1 S
P L S 848
1972

from which the remains of the original bearing trees:

A larch snag, 18 ins. diam., bears S. 77° E., 26 lks. dist., with scribe marks T1S R36E S6 BT visible on open double blaze. (Record, S. 74° E., 24 lks.)

A decayed fir stump, size indeterminate, bears S. 24° W., 41 lks. dist., no marks visible.

And bearing trees mkd. by Ferguson:

A fir, 14 ins. diam., bears N. 35° E., 65 lks. dist., with healed blaze.

A fir, 10 ins. diam., bears S. 33° E., 25 lks. dist., with healed blaze.

A spruce, 15 ins. diam., bears S. 23° W., 75 lks. dist., with partially healed blaze.

Add marks AM to brass cap.

MONUMENT AND ACCESSORIES FOUND:

Found a 3" BLM brass cap on a 2 1/2" galvanized iron pipe, 2" above ground level, in good condition, marked as shown in monument marking detail, from which:

A 12" Douglas fir bears S 15 1/2° E, 19.8 feet, with visible scribes. (BLM bearing tree).

A 22" Douglas fir bears S 52° W, 29.0 feet, with visible scribes. (BLM bearing tree).

The Ferguson amended closing corner monument bears North 0°31' E., 3.80 feet from BLM true closing corner monument. The Ferguson cap is unreadable because of a 30" felled tree covering it.

A 18" fir bears N 31° E, 47.0 feet with healed blaze. (Ferguson bearing tree).

A 12" fir bears S 42 1/2° E, 13.5 feet with healed blaze. Ferguson bearing tree).

A 15" spruce bearing tree bears approximately S 23° W, 46 feet. This tree is uprooted and is dead, lying on ground. (Ferguson bearing tree).

The western larch snag, referencing the original closing corner remonumented by Ferguson, still stands with visible scribes on open double blaze.

MONUMENT MARKING DETAIL:

DEPT OF THE INTERIOR
T1N R36E S31
S31
S1 | S6
R35E | R36E
T1S
C C
1984
BLM

LOCATION AND COMMENTS:

STATE PLANE CO-ORDINATES:

Oregon North, NAD 83/91, International Foot:

BLM True CC: N= 681086.37 Ferguson Amended CC: N: 681090.17
E=8749089.56 E:8749089.49

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT
Mark Hammersla

TIS35A25

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-02

RECEIVED BY
Umatilla County Surveyor
Date 11-01
Rec'd By KK
No. 01-177-R