


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:  
Corner not previously established.



No record of subsequent monumentation found in Umatilla County survey records.

Description of corner evidence found:

Corner not previously established.  
See map of survey dated September, 1989.

Description of monument and accessories I established to perpetuate the original location of this corner: At position determined by survey, I set a 2 1/2" x 30" aluminum pipe with aluminum cap marked as shown, 30 inches in the ground, from which:

New Bearing Trees:  
A 8 inch diameter Spruce bears S15°E, 25.55 feet marked E 1/16 S1 BT  
A 9 inch diameter Western Larch bears S41°W, 18.73 feet marked E 1/16 S1 BT

Painted a 6 inch red band around all BTs and attached bearing tree and land survey monument signs.

Set a steel fence post approximately 5 feet South with Land Survey Monument and Property Boundary signs attached.

I hereby certify that the above corner point was perpetuated as hereon described on August 15, 1989.

Witnesses: Jeff Petersen and Rick Robinson.



I used a steel tape and magnetic compass in the establishment of new accessories. I used 17° East magnetic declination and the distances are to a 50d spike driven in the right side of the root crown. I attached a brass washer marked OPLS 644 to the BT blaze.

Office of the Survey Dept. County of Umatilla  
State of OR I hereby certify that the within instrument was filed in this office  
for record on the 27<sup>th</sup> day of October, 1989  
Duane I. Griffith by Richard H. Kumbstein (COUNTY OFFICIAL) Richard H. Kumbstein (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor

Date 10-89

Received by KA

No. 89-101-B

\*GPO-591-971, 1988