


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by Herman D. Gradon under GLO contract number 452, dated June 16, 1882. Surveyor General record states:

Set a post 3 ft. long 3 ins square 24 ins in the ground for 1/4 sec cor marked 1/4 S on N face from which;  
A spruce 7 ins diam bears N40°W 24 lks dist marked 1/4 S BT  
A spruce 7 ins diam bears S30°W 13 lks dist marked 1/4 S BT



No record of subsequent monumentation found in Umatilla County survey records.

Description of corner evidence found:

Found no evidence of the original corner monument or it's accessories.

See map of survey dated September, 1989.

Description of monument and accessories I established to perpetuate the

original location of this corner: At position determined by survey, I set a 2 1/2" x 30" aluminum pipe with aluminum cap marked as shown, 24 inches in the ground, from which:

New Bearing Trees;

A 8 inch diameter Western Larch bears S58°E, 14.27 feet marked 1/4 S12 BT  
A 15 inch diameter Western Larch bears N1°W, 28.27 feet marked 1/4 S1 BT

Painted a 6 inch red band around all BTs and attached bearing tree and land survey monument signs.

Set a steel fencepost approximately 5 feet North with land survey monument and property boundary signs attached.

Raised mound of stone around monument, 3 ft. base to top of cap.

I hereby certify that the above corner point was perpetuated as hereon described on August 15, 1989.

Witnesses: Jeff Petersen and Rick Robinson



I used a steel tape and magnetic compass in the establishment of new accessories. I used 17° East magnetic declination and the distances are to a 50d spike driven in the right side of the root crown. I attached a brass washer marked OPLS 644 to the BT blaze.

Office of the Survey Dept County of Umatilla  
State of OR I hereby certify that the within instrument was filed in this office  
for record on the 27<sup>th</sup> day of October 1989  
David H. Kumbien by Jeffrey Petersen  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

\*GPO-591-971, 1988

RECORDED BY  
Date 10-89  
Rec'd By JA  
No. 89-101-B