


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: Corner established by Jacob C. Cooper in 1881 under General Land Office Contract No. 397.



Surveyor General Records (notes) states:

- A tamarack 12 in. diam. on the south side of mountains 200 ft. below the summit in dense young timber which I marked for the 1/4 Section Corner, marked 1/4S on the East and West faces from which
- A fir 6 in. diam. bears S28°E, 14 lks. dist. marked 1/4S BT.
- A pine 12 in. diam. bears N78°W, 22 lks. dist. marked 1/4S BT.

Corners for T1S R37E were set in subsequent survey.

(No subsequent remonumentations in county records)

Description of corner evidence found:

- Found a 24 in. tamarack with grown-over blazes on 4 sides, live, in good condition.
- Found a 24 in. fir, live in good condition, with scribing visible, bearing S28°E 9 ft. from corner tree.
- Found a 24 in. pine stump with scribing faintly visible, bearing N78°W 14 ft. from corner tree.

Description of monument and accessories established to perpetuate the original location of this corner

- No monument set as tree is in good condition, for East 1/4 Cor. Sec. 12
- From which a new BT
- A tamarack 20in. diam. bears S87°W, 63.5 ft. dist. marked T1S, R36E, 1/4S 12 BT.
- Distance taken to a brass washer in the blaze of the tree.
- Set a steel fence post approximately 5 ft. west from original corner tree with Forest Boundary sign attached.
- Used steel tape and magnetic compass with declination = 20°E.



Office of Surveyor County of Wasilla  
 State of Alaska, I hereby certify that the within instrument was filed in this office  
 for record on the 16 day of April, 1976, at 10 o'clock am, (signed)  
Douglas M. Ferguson by \_\_\_\_\_ (DEPUTY)  
 (COUNTY OFFICIAL)