


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

H-149  
21

History of original corner establishment: Corner established in 1882 by Herman D. Gradon, under General Land Office Contract No. 452.



Survey General Records (notes) states:

Set a basalt stone 12 x 10 x 5 ins. 8 ins. in the ground for 1/4 Sec. Cor. marked 1/4 on W face, from which,

- A pine 18 ins. diam. bears S75°E 89 lks. dist. marked 1/4 S BT.
- A pine 6 ins. diam. bears S60°W 67 lks. dist. marked 1/4 S BT.

L-21

(No subsequent remonumentations in county records)

**Description of corner evidence found:**

Found 30 in. pine standing in good condition, grown over blaze clearly visible, bearing S60°W 44.2 ft. from corner position.

Found an 18 in. pine stump with all scribing clearly visible, bearing S75°E 58.8 ft. dist. from the corner position.


**Description of monument and accessories I established to perpetuate the original location of this corner**

Set a 30 in. x 2 1/2 in. iron pipe with 3 in. brass cap marked as shown 25 in. in the ground for the 1/4 Sec. Cor. between Sec. 14 & 13 from which a new BT -

- A 18 in. ponderosa pine bears S44°E 26.8 ft. dist. marked T1S R36E 1/4 S13 BT.

Distance taken to a brass washer in the blaze of the tree. Set a steel fence post approximately 5 ft. East from corner with Forest Boundary sign attached.

Used steel tape and magnetic compass with declination = 20° East.



REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Douglas M. Ferguson*

OREGON  
JULY 12, 1939  
DOUGLAS M. FERGUSON  
848

Office of Sunnyvale County of Washtenaw  
 State of Oregon, I hereby certify that the within instrument was filed in this office  
 for record on the 15th day of July, 1972, at 10 o'clock a.m., (signed)  
Douglas M. Ferguson by \_\_\_\_\_ (DEPUTY)  
 \_\_\_\_\_ (COUNTY OFFICIAL)

H-149