


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: Corner established in 1882 by Herman D. Gradon, under General Land Office Contract No. 452.

Surveyor General Records states:
Set a basalt stone 16 x 12 x 4 ins. 11 ins. in the ground for 1/4 Sec. Cor. marked 1/4 on N face from which a pine 5 ins. diam. bears N 15° E 62 lks. dist. marked 1/4 S BT. No other tree within limits and raised a mound of stone alongside.



N-7

(No subsequent remonumentations in county records)

Description of corner evidence found:


Found 8 in. pine dead and down with scribing visible. Bearing N15°E 41 ft. from 16 x 12 x 4 ins. stone with chipped face. Stone is tipped over on steep ground. Established corner position at stone.

Description of monument and accessories established to perpetuate the original location of this corner

Set 2 1/2 in. x 30 in. iron pipe with brass cap marked as shown 25 in. in the ground and placed 16 x 12 x 4 in. stone South and alongside pipe for the 1/4 corner to Sections 17 and 20 and raised a mound of stone around the pipe, from which a new BT - a 24 in. pine bears N 50° W 63.8 ft. dist. marked T1S R36E 1/4 S 17 BT. Distance taken to a brass washer in the blaze of the BT.

Set a steel fence post approximately 5 ft. West of corner with "Attention" sign attached.

Corner laying on open E-W ridge sloping East.



Used steel tape and magnetic compass with declination = 20° East.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Douglas M. Ferguson
OREGON
JULY 12, 1963
DOUGLAS M. FERGUSON
848

Office of *Sumner* County of *Umatilla*
State of *Oregon*, I hereby certify that the within instrument was filed in this office for record on the *15th* day of *September*, 19*72*, at *10* o'clock *am*, (signed) *Douglas M. Ferguson* by *Douglas M. Ferguson* (DEPUTY)