


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

13
1

History of original corner establishment: Corner established in Oct. 1882 by Herman D Gradon, under General Land Office Contract No. 452.

Surveyor General records (notes) states:
Set a basalt stone 20x20x10 ins. 15 ins. in the ground for cor. to secs. 19, 20, 29, & 30 marked with 2 notches on South and 5 notches on the East edges, from which:




- A pine 28-ins. diam. bears E 40° E, 76 lks. dist. marked T 1 S, R 36 E, S 20 B.T.
- A fir 4 ins. diam. bears S 50° E 16 lks. dist. marked T 1 S, R 36 E, S 29 B.T.
- A pine 20 ins. diam. bears S 55° W 43 lks. dist. marked T 1 S, R 36 E, S 30 B.T.
- A pine 18 ins. diam. bears N 75° W 26 lks. dist. marked T 1 S, R 36 E, S 19 B.T.

R-5

Description of corner evidence found:
 Found a 30" pine stump, with all scribing visible, bearing N40°E 49 ft. dist. from the corner position.
 Found a 26" pine, live in good condition with scribing visible, bearing S 55°W 27.0 ft. dist. from corner position.
 Found the remains of a pine stump, rotted off flush with the ground, bearing N75°W 17.2 ft. dist. from the corner position.

Description of monument and accessories established to perpetuate the original location of this corner

- Set 30"x2 1/2" iron pipe, with 3" brass cap marked as shown, 23" in the ground & placed stones around pipe for the cor. to sections 19, 20, 29 & 30. From which now bearing trees.
- A Fir 20 ins. diam. bears N10°E 23.3 ft dist., marked T1S R36E S20 BT.
- A Fir 16 ins. diam. bears S58°E 56.2 ft Dist., marked T1S R36E S29 BT.
- A Fir 10 ins. diam. bears N68°W 41.4 ft. dist., marked T1S R36E S19 BT.
- All distances taken to a brass washer in the blaze of each tree
- Set a steel fence post approx. 5 ft. east from corner with Forest Boundary Sign attached.
- Used a steel tape & magnetic compass with declination equal 200 East.



REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 12, 1938
DOUGLAS M. FERGUSON
848

Office of Sherwood County of Clatsop
 State of Oregon, I hereby certify that the within instrument was filed in this office for record on the 11th day of April, 1974 at 10 o'clock am, (signed)
Douglas M. Ferguson by _____ (DEPUTY)