


R-6

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

This corner establishment was not recorded in the county records, but the evidence on the ground consists of a 5/8-inch rebar and two bearing trees. The 5/8-inch rebar is S. 58° 14' 24" E., 118.09 ft. dist. from the true location determined by the survey by the undersigned.



R-7

Description of corner evidence found:

Described above.

Description of monument and accessories established to perpetuate the original location of this corner

Set a 2½-inch brass cap on a 2-inch iron pipe 31 inches long, 6 inches above ground in an earth and rock mound, with steel fence post and sign 54-4 alongside.

Monument marked:

T 1 S	R 36 E
	S 20
W 1/16	—
	S 29
RPE 2808	
1976	

A fir 12" diam. bears S 13° W, 16.5 ft. dist., mkd. W 1/16 S 29 BT.

A fir 6" diam. bears N 20° E, 57.0 ft. dist., mkd. W 1/16 S 20 BT.

Office of Surveyor County of Umatilla
 State of Oregon I hereby certify that the within instrument was filed in this office
 for record on the 26 day of August, 1976.
 by
 (COUNTY OFFICIAL) (DEPUTY)

