

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


History of original corner establishment:

Survey by Herman D. Gradon under contract No. 452, dated June 16, 1882.

Set a basalt stone 24 x 18 x 6 ins. 18 ins. in the ground for 1/4 sec. cor. mkd. 1/4 on the N face from which:

A pine, 11 ins. diam. bears N 62° E, 62 lks. dist., mkd. 1/4 S BT.

A pine, 12 ins. diam. bears S 74° E, 119 lks. dist., mkd. 1/4 S BT.



Description of corner evidence found:

None

Description of monument and accessories established to perpetuate the original location of this corner

Set a 2 1/2-inch brass cap on a 2-inch iron pipe 31 ins. long in an earth and stone mound with a 6 ft. steel fence post alongside with sign 54-4 attached. Scribbed two bearing trees:

A pine, 8" diam., bears N 83° E, 46.0 ft. dist., mkd. 1/4 S 20 BT.

A pine 10" diam., bears S 37° E, 36.2 ft., dist., mkd. 1/4 S 29 BT.

Monument marked:

T 1 S R 36 E
 1/4 S 20
 S 29
 RPE 2808
 1976



Office of Surveyor County of Umatilla
 State of Oregon, I hereby certify that the within instrument was filed in this office
 for record on the 26 day of August, 1976
 _____ by _____
 (COUNTY OFFICIAL) (DEPUTY)