


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: Corner established in 1882 by Harrah D. Bradon under General Land Office Contract #1452



Surveyor General Records (notes) states:
Set a post 4 ft. long, 4 ins. square, 24 ins. in the ground for Cor. to Sec. 20, 21, 28, & 29 marked S21 on NE R36E S28 on SE S29 on SW and S20 on NW faces, with 2 notches on S and 4 notches on E edges from which a fir 8ins. dia. bears N 40° E 44 lks. dist. marked T1S R36E S 21 BT.

(no subsequent remonumentations in county records)


- A fir 10 ins. dia. bears S 50° E 37 lks. dist. marked T1S, R36E S28 BT
- A fir 14 ins. dia. bears S 63° W 27 lks. dist. marked T1S, R36E S29 BT
- A fir 8 ins. dia. bears N 50° W 33 lks. dist. marked T1S, R36E S20 BT

Description of corner evidence found:

Found 30" fir alive in good condition with scribing visible, bearing S 63° W 17.9 ft. distance from the corner position.
Found remains of a fir, no scribing visible. Bearing N 50° W 22 ft. distance from the corner position.
Established corner position from live 30" fir.

Description of monument and accessories established to perpetuate the original location of this corner

Set 30"x2 1/2" iron pine with 2" brass cap marked as shown 26" in the ground for the corner to Sec. 20, 21, 29, & 28 from which new BT's
A 12" lodge pole pine bears N 65° E 15.7 ft. dist. marked T1S R36E S21 BT
A 12" fir bears S 57° E 39.2 ft. dist. marked T1S R36E S28 BT
A 12" fir bears N 46° W 17.3 ft. dist marked T1S R36E S20 BT
All distances taken to a brass washer in the blaze of each tree.
Set a steel fence post approximately 5' west of corner with Forest Boundary sign attached.



REGISTERED PROFESSIONAL LAND SURVEYOR

Used steel tape and magnetic compass with declination = 20° E

OREGON
JULY 12, 1973
DOUGLAS M. FERGUSON
843

Office of S. J. [Signature] County of Umatilla
State of Oregon I hereby certify that the within Instrument was filed in this office for record on the 14th day of July, 1972, at 10 o'clock a.m., (signed) [Signature] by [Signature] (DEPUTY)