

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

H-164


16

**History of original corner establishment:**

Corner established in Oct. 1882 by Herman D. Gradon, under General Land Office Contract No. 452.

Surveyor General records (notes) states:

Set a basalt stone 13x10x8 ins. 9 ins. in the ground for the corner to secs. 28, 29, 32 & 33, marked with 1 notch on the South and 4 notches on the East edges, from which a Pine 8 ins. dia. bears N. 35° E. 57 lks. dist. marked T 1 S, R 36 E., S 28 B.T.



A Pine 5 ins. dia. bears S. 40° E., 43 lks. dist. marked T 1 S, R 36 E., S 33 B.T.

A Pine 7 ins. dia. bears S 30° W 26 lks. dist. marked T 1 S, R 36 E., S 32 B.T.

A Tamarack 24 ins. dia. bears N 40° W 20 lks. dist. marked T 1 S, R 36 E., S 29 B.T. note: No restoration appears in the county records.

V-9

**Description of corner evidence found:**

Found 13"x10"x 8" basalt stone with 4 faint notches . Stone is laying on surface approx. 4 ft. south from corner position as determined by Bearing Trees.

Found live healthy 30 ins. tamarack marked T1S R36E S29 BT visible, bearing N60°W 13.2 ft dist. from the corner position.

Found down & dead lodge pole pine, 14 ins. dia. marked T1S R36E S28 BT, visible, bearing N35°E 37.6 ft. dist. from the corner position

Found remains of pine with faint scribing visible, indentation where tree apparently stood bears S40°E 28.0 ft. from corner position.

Found line blazes running south.

**Description of monument and accessories established to perpetuate the original location of this corner**

Set 30"x2 1/2" iron pipe with 3" brass cap marked as shown, 26" in the ground & placed the original stone south & alongside pipe, for the corner to sections 28, 29, 32 & 33 as determined from the above evidence, & raised a mound of stone around the pipe.

From which new Bearing Trees.

A Lodge pole Pine 12 ins. diam. bears N40°E 40.3 ft. dist. marked T1S R36E S28 BT.


A Lodge Pole Pine 9 ins. diam. bears S25°E 38.3 ft. dist. marked T1S R36E S33 BT

A lodge Pole Pine 8 ins. diam. bears S47°W 37.7 ft. dist. marked T1S R36E S32 BT

Distances taken to a brass washer in the blazes of each tree

Set a steel fence post approx. 5 ft. west from pipe with Forest Boundary Sign attached.

Used a steel tape & magnetic compass with declination equal 9° East



REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

---

OREGON  
JULY 16, 1933  
DOUGLAS M. FERGUSON  
848

Office of \_\_\_\_\_ County of Washtenaw  
 State of Michigan, I hereby certify that the within instrument was filed in this office  
 for record on the 14th day of July, 1972, at \_\_\_\_\_ o'clock \_\_\_\_\_ m., (signed)  
 \_\_\_\_\_ by \_\_\_\_\_ (DEPUTY)

H-164