


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by Henry Meldrum under GLO contract number 450, dated June 11, 1882. Surveyor General record states:

Set basalt stone 18x10x4 ins 12 in in ground for closing corner to Secs 5 + 6 marked CC with 5 notches on E and 1 on W edges, from which;

- A pine 40 in diam bears S16°W 54 lks dist marked R37E S6 BT
- A pine 4 in diam bears S32°E 44 lks dist marked T1S S5 BT
- A pine 7 in diam bears N7°W 31 lks dist marked T1N S32 BT



No record of subsequent monumentation found in Umatilla County survey records.

Description of corner evidence found:

Found no evidence of the original corner monument.

Found a stump hole S32°E, 44 lks.

Found a 48 inch diameter Ponderosa Pine S16°W, 54 lks, live with a chop mark only visible evidence.

Found a rotted out Ponderosa Pine stump hole N7°W, 31 lks with piece of wood with scribe alongside.

Description of monument and accessories I established to perpetuate the

original location of this corner: At record bearing and distance from the above described found original bearing trees, I set a 2½" x 30" aluminum pipe with aluminum cap marked as shown, 26" inches in the ground, from which:


New Bearing Trees:

- A 12 inch diameter Douglas Fir bears S31°E, 36.3 feet marked T1S R37E S5 CC BT
- A 16 inch diameter Douglas Fir bears S17°W, 26.67 feet marked T1S R37E S6 CC BT

Painted a 6 inch red band around all BTs and attached bearing tree and land survey monument signs.

Set a steel fencepost approximately 5 feet East with land survey monument sign attached.

I hereby certify that the above corner point was perpetuated as hereon described on September 5, 1989.



I used a steel tape and magnetic compass in the establishment of new accessories. I used 17° East magnetic declination and the distances are to a 50d spike driven in the right side of the root crown. I attached a brass washer marked OPLS 644 to the BT blaze.

Office of... the Survey Dept. ... County of... Umatilla ...
 State of... OR ... I hereby certify that the within instrument was filed in this office
 for record on the 27 day of... October ... 1989.
David H. Kumbstein ... by Kathleen Kumbstein ...
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

*GPO-591-971, 1988

10-89
 No. 89-106-R