


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by Henry Meldrum under GLO contract number 450, dated June 11, 1882. Surveyor General record states:
Set basalt stone 16x10x7 ins 12 in in ground for cor to secs 19 + 30 marked with 2 notches on S + 4 on N edges, from which;

A pine 5 in diam bears N47°E 20 lks dist marked T1S S19 BT
A pine 18 in diam bears S74°W 47 lks dist marked R36E BT
A pine 24 in diam bears S50°E 85 lks dist marked R37E S30 BT



No record of subsequent monumentation found in Umatilla County survey records.

Description of corner evidence found:

Found a stone 14x9x6 inches marked with 4 grooves on one face, 2 grooves on one face and 6 grooves on one face. Stone is in a recently made mound of stone approximately 4 feet Southeast of the true corner position as located by pulling the record distance from the found original bearing trees.

ORIGINAL BEARING TREES

Found a 27 inch diameter Ponderosa Pine N39°E, 20 lks live and vigorous with scribes visible. (Record N47°E)

Found a 28 inch diameter Ponderosa Pine S55°E, 85 lks live and vigorous with scribes visible. (Record S50°E)

Found a rotted Ponderosa Pine snag S74°W, 47 lks with scribes visible.

Distances to the original BTs are to the estimated face of blaze.

Description of monument and accessories | established to perpetuate the

original location of this corner: At record distance from the found original bearing trees, I set a 2 1/2" x 30" aluminum pipe with aluminum cap marked as shown, 8 inches in the ground, from which:

Raised mound of stone around monument, 5 ft. base to top of cap.

Painted a 6 inch red band around all BTs and attached bearing tree and land survey monument signs.

Set a steel fencepost approximately 5 feet North with land survey monument sign attached.

Buried the original corner stone West and alongside of monument.

I hereby certify that the above corner point was perpetuated as hereon described on August 4, 1989.

Witnesses: Jeff Petersen and Rick Robinson



REGISTERED PROFESSIONAL LAND SURVEYOR

Duane I. Griffith

OREGON
JULY 10, 1964
DUANE I. GRIFFITH
644

I used a steel tape and magnetic compass in the establishment of new accessories. I used 17° East magnetic declination and the distances are to a 50d spike driven in the right side of the root crown. I attached a brass washer marked OPLS 644 to the BT blaze.

Office of The Survey Dept. County of Umatilla
State of OR I hereby certify that the within instrument was filed in this office for record on the 27th day of October, 1989
David H. Raumborn by Kathleen K. Knosberg
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECORDED BY

Umatilla County Surveyor

Date 10-89

Book KA

No. 89-106-L

*GPO-591-971, 1988