

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 04/21/17.

CORNER DESIGNATION: E-5, The Southeast corner of Section 6, Township 2 North, Range 28 East, W.M..

PREVIOUS RENEWALS/SURVEYS ETC: Corner originally established by David P. Thompson Contract No. 83 dated July 22, 1859. Notes state: Set post corner for corner to Secs. 5, 6, 7 and 8 in mound of earth & as per instructions. The corner was reestablished by John Kimbrell, Deputy County Surveyor, in Survey No. 357, recorded at Record of Private Survey Book 2, Page 216, in December, 1912. Kimbrell reports setting a marked square wood post 18" in the ground at the corner point.

MONUMENT AND ACCESSORIES FOUND: None. I reestablished this corner by double proportionate measurement using the 1912 Kimbrell Record.

MONUMENT MARKING DETAIL:

T2N R28E
S6 | S5

S7 | S8
2017
PLS 1106

MONUMENT SET: At the reestablished corner point, set a 1 1/4" by 30" galv. iron pipe with 2 3/8" brass cap 28" in the ground and surrounded with four stones. Cap is marked as shown in "Monument Marking Detail".

New accessories:

- A 5/8" by 24" rebar with 1 1/4" red plastic cap bears N 39° E, 34.2 feet.
- Most Northerly of two guywires anchoring a guy pole bears S 45° E, 30.5 feet. Measured to where guywire enters the ground.
- A 5/8" by 30" rebar with 1 1/4" red plastic cap bears S 44° W, 33.8 feet.
- A 5/8" by 24" rebar with 1 1/4" red plastic cap bears N 36° W, 32.9 feet.

Red plastic caps are marked "ORPLS 1106 WAPLS 17372". Wired "bearing object" signs to the rebar accessories. Set steel fence post 2 feet South of corner with "witness" sign wired to it.

LOCATION AND COMMENTS: Corner falls about 45' North of Eagle Ranch Road.

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

\2N28E5

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-18