

OREGON CORNER RESTORATION FORM

Section 33 Township 3N
County Umatilla Date: 03/08/10

Range 29E

Corner Designation: 3N29Z11

1/4 Corner common to sections 33 T3NR29E, 4 T2NR29E.

_____	Condition Report Only
_____X_____	Not Found
_____X_____	Remonumented
_____	Unrecorded
_____X_____	Surveyed In
_____X_____	Referenced Out


Previous Renewals / Surveys, etc.

Originally Surveyed by David P. Thompson. He set a post in a mound of earth in 1859.
1 1/4" pipe set by Harris in Survey No. Q-76-B.

Monuments and Accessories Found: (Condition and Source)

Held distances called on Harris survey and found 1 1/4" pipe lying flat below the surface, in plowed field within a foot of it's called distance. Reset from Calls.

Diagram



Sketch

- Orange Magnet
- Silver Magnet
- 2 1/2" BC
- 5/8" rebar with sfp ●x
- Blue Magnet

NAD 83/91
OREGON STATE PLANE NORTH
INTERNATIONAL FEET

N740229.38
E8535717.19

LAT - 45° 41' 22.71518" N
LON - 119° 11' 39.95536" W

Monument (s) Set (Procedures and Description)

Set a 1 1/4" x 30" galvanized iron pipe with a 2 1/2" brass cap, stamped as shown above. The monument is 18" deep. In farm field on Northeasterly facing slope.

References Set: "Deep One" magnets by Berntsen.

- An Orange magnet, 18" deep lies N 58°10' W, 19.71'.
- A Silver magnet, 18" deep lies N 11°20' E, 20.75'.
- A 5/8"x30" Iron rebar w/ypc #43406 lies N 89°30' E, 60.00', on line, at edge of field.
- A Blue magnet, 18" deep lies S 9°20' W, 17.18'.

Location and Comments

The corner is 2.0 miles East of the cattle guard at the South end of Snow Road along the East-West fence.

Compass Declination
17° E

Surveyors Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Robert D. English
OREGON
JANUARY II, 2005
ROBERT DOUGLAS ENGLISH
43406LS

RECEIVED BY:

Date: 1-11
Rec'd By: RK
No. 11-21-12

Firm / Agency

Survey One, LLC.
P.O. Box 382
Pendleton, OR 97801
(541) 276-2055

RENEWAL DATE: 12/31/11