

OREGON CORNER RESTORATION FORM

Section 31

Township 3N

Range 29E

County Umatilla

Date: 01/15/10

Corner Designation: 3N29Z5

Corner common to sections 31,32 T3NR29E, 5,6, T3NR28E.

- Condition Report Only
- Not Found
- Remonumented
- Unrecorded
- Surveyed In
- Referenced Out


Previous Renewals / Surveys, etc.

Originally Surveyed by David P. Thompson. He set a post in a mound of earth in 1859.

Monuments and Accessories Found: (Condition and Source)

- A 2 3/8" Brass cap w/ 951 stamp, no record.
- A 1" Iron rebar w/ypc 951LS lies N 67°00' E, 114.52'.
- A 1" Iron rebar w/ypc 951LS lies N 18°00' E, 41.26'.
- A 1" Iron rebar w/ypc 951LS lies N 33°15' W, 44.33'.
- A 1" Iron rebar w/ypc 951LS lies N 66°15' W, 82.61'.

Diagram



Sketch



2 3/8" BC



NAD 83/91
OREGON STATE PLANE NORTH
INTERNATIONAL FEET

N740003.66
E8527775.22
LAT - 45° 41' 21.73890" N
LON - 119° 13' 31.87416" W

Monument (s) Set (Procedures and Description)

None

References Set:

None

Location and Comments

The corner is 1/2 mile West of cattle guard near the South end of Snow Road and 45 feet South of old fence.

Compass Declination

17° E

Surveyors Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Robert D. English
OREGON
JANUARY 11, 2005
ROBERT DOUGLAS ENGLISH
43406LS

RECEIVED BY:

Date: 1-11
Rec'd By: RE
No. 11-21-R

Firm / Agency

Survey One, LLC.
P.O. Box 382
Pendleton, OR 97801
(541) 276-2055

RENEWAL DATE: 12/31/11