

OREGON CORNER RESTORATION FORM

SECTION: 17 TOWNSHIP: 2N RANGE: 29E J-9

COUNTY: UMATILLA DATE: 8/2010

CORNER DESIGNATION

NE 17

- CONDITION REPORT ONLY
- NOT FOUND
- RENEWED
- UNRECORDED
- SURVEYED IN
- REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS ETC.

Originally surveyed by Thompson under Contract #83 in 1859. He set post and made mound.

MONUMENTS AND ACCESSORIES FOUND: CONDITON AND SOURCE

Nothing found.

MONUMENT DETAIL

T2N R29E
 8 | 9
 17 | 16
 2008
 LS 951

OREGON STATE PLANE COORDINATES NORTH ZONE, NAD 83(91), Int Feet:

729492.60
 8533228.74

MONUMENT SET (PROCEDURES AND DESCRIPTION)

By double proportion I set a 2 3/8" brass cap on a 1" x 30" iron pipe 3" above surface and placed stones around.

NEW ACCESSORIES FROM WHICH

- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 57° 14' 45" E 78.62'
 - A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 58° 43' 34" E 78.71'
 - A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 44° 00' 36" W 51.48'
 - A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 36° 52' 38" W 66.32'
- These bearings and distances are State Plane.

LOCATION AND COMMENTS

From the intersection of the Heppner to Echo Highway with Snow Road go South on Snow Road 5.1 miles. Corner lies 0.5 mile East in a small ravine.

SURVEYOR'S SEAL

FIRM: EDWARDS SURVEYING LLC
 PO BOX 763 - HERMISTON OR 97838

PARTY CHIEF: G. EDWARDS
 WITNESS: R. SMITH

