

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 11/23/09

CORNER DESIGNATION: A-19, The North one-quarter Corner of Section 2, Township 2 North, Range 30 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner originally established by David P. Thompson, Deputy Surveyor under his contract dated July 22, 1859. Notes state: Set post for 1/4 Sec. corner in mound of earth with pits and trenches as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R30E
1 S35
4 S2
T2N
2009
PLS 1106

MONUMENT SET: Calculated position for the one-quarter corner midway between recovered Section Corners East and West. At the corner position, set a 2 3/8" dia. brass cap on a 1 1/4"x30" galvanized iron pipe with cap 2" above ground level in small mound of earth. Cap is marked as shown in "Monument Marking Detail".

New accessories:

A 5/8"x24" dia. iron rebar with 1 1/4" red plastic cap marked "ORPLS 1106 WAPLS 17372" in East-West fence bears (Grid Azimuth) 56°, 28.6 feet.

A 5/8"x24" dia. iron rebar with 1 1/4" red plastic cap marked "ORPLS 1106 WAPLS 17372" bears (Grid Azimuth) 118°, 44.9 feet.

A 5/8"x24" dia. iron rebar with 1 1/4" red plastic cap marked "ORPLS 1106 WAPLS 17372" in North-South fence bears (Grid Azimuth) 275°, 75.1 feet.

A 5/8"x24" dia. iron rebar with 1 1/4" red plastic cap marked "ORPLS 1106 WAPLS 17372" in East-West fence bears (Grid Azimuth) 307 1/2°, 22.7 feet.

All distances are ground. Set steel fence post with Witness sign 1 foot North of corner monument and attached bearing object signs to all iron rebar. Rotate grid azimuths 1.0° clockwise to get to azimuths from true North.

LOCATION AND COMMENTS: Corner is located 2" above ground level approximately 12 feet South of a crooked East-West running fence line.

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

2N30A19

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-10

RECEIVED BY

Umatilla County Surveyor

Date 12/09

Rec'd By [Signature]

No. 09-172-C