

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 02/01/06

CORNER DESIGNATION: 3N31, Z13, The Southwest Corner of Section 34.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Josiah A. Burnett, under Contract No. 92, dated September 12, 1860. Record states: Set a post for corner to Secs. 3, 4, 33 & 34. Drove charred stake and raised mound with trench, as per instructions. This corner was remonumented by Don Staebler, PLS 1333, under Survey No. 88-61-C. Staebler's corner restoration for states: "I found 1 1/4" G.I.P. I set in 1973 from the Oregon State Highway Dept ties (sta T60+57.50)."

MONUMENT AND ACCESSORIES FOUND:

Found 2 1/2" brass cap on galv. iron pipe monument, marked as shown, 10" below road surface, from which:

A 5/8" rebar with red plastic cap bears N 72 1/4° E 83.67 feet.

A 5/8" smooth rebar bears N 69° W 69.82 feet.

MONUMENT MARKING DETAIL:

T3N R31E
S33|S34
S4|S3
T2N
1988
RLS 1333

NEW ACCESSORIES:

A 5/8" x 24" iron rebar with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", bears North 42 1/2° East, 52.4 feet.

A 2" tube steel road sign post bears South 03° East, 11.1 feet. Measured to where post goes into ground, about 3 feet higher than monument. Wired witness sign to sign post.

Attached bearing object signs to all accessories.

LOCATION AND COMMENTS:

Corner is located in the centerline of Fansier County Road at its intersection Barnhart Road running North.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 741408.64
E = 8602409.15

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

/3N31Z13



William R. Wells
OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-08