

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 04/03/06

CORNER DESIGNATION: 2N31, C-21, The West One-Quarter Corner of Section 1.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner established by Josiah A. Burnett, under Contract No. 92, dated September 12, 1860. Record states: Set a post for 1/4 Sec. corner, drove charred stake and raised mound with trench, as per instructions. State Highway Department freeway right-of-way and monumentation maps for Interstate 84 show a state plane coordinate (NAD 1927) for this corner. The maps do not indicate what was recovered.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T2N R31E
1
4
S2 | S1
2006
PLS 1106

MONUMENT SET:

Re-established corner position using indexed Oregon State Highway Department freeway map coordinates, after indexing State coordinates to our State Plane measurement values at freeway centerline monuments at 930+94.45 and 985+59.60. At reestablished corner position, set a 2 3/8" brass cap on 1 1/4" x 30" galvanized iron pipe with cap 15" below ground level in a farmed field. Monument marked as shown in monument marking detail.

From which:

A silver Deep-1 magnet buried 22" below ground level bears North 50 1/2° East, 28.0 feet.
A blue Deep-1 magnet buried 22" below ground level bears South 28 1/2° East, 32.6 feet.
A purple Deep-1 magnet buried 22" below ground level bears South 49 1/2° West, 33.0 feet.
An orange Deep-1 magnet buried 22" below ground level bears North 33° West, 26.6 feet.
Buried bearing object signs with all magnets.

LOCATION AND COMMENTS: Corner is located in a farmed field. There are no definite features near the corner area.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 738818.10
E = 8613035.86

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

/2N31C21

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-08

06-462-c