

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

E - 25
DIAGRAM

History of original corner establishment:

The original corner was established by David P. Thompson, as part of a guide meridian, on August 7, 1859, under GLO contract No. 81, as follows:
Set a post for section corner and build a mound of earth with pits & trench, & etc., per instructions.



On September 1, 1904, County Surveyor John W. Kimbrell reestablished this corner position by proportionment measurement at 119.75 chains north of 1/4 S13|S18, as follows:
Set a stone, 18" x 7" x 6", for the corner to sections 1, 6, 7 and 12.

On February 10 through the 13, 1915, County Surveyor Willard Bradley conducted a survey of the guide meridian and at this corner he found the following:
Found old stakes in ground and two small stones at a point about six feet north of a fence corner. This point is accepted by all present as good indications of the corner. Set a large stone and made a stone mound.

On June 15, 1999, Gary B. Wagner, PLS 2817, found and accepted a fence corner as the position of this corner. See County Survey Map No. 99 - 133 - B.

Original corner evidence recovered:

Found a basalt stone solidly set 19" into the ground and surrounded by a mound of stones. The corner stone is 23" x 11" x 9" and is plainly marked with five grooves on the south face, one groove on the north face and a "+" on the top. Based on the size of this stone, I accept it as the stone set by County Surveyor Bradley in 1915.

Monument and accessories established to perpetuate the original position of this corner:

In place of the corner stone, I set a 1" x 30" flared, galvanized iron pipe 25" into the ground. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above. I bury the corner stone to the south side of the pipe and build a mound of stones around the pipe, from which:
A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S6", attached at ground level, bears N32° 30'E, 116.0 feet.
A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S7", attached at ground level, bears S54° 30'E, 63.6 feet.
A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 12", attached at ground level, bears S69° W, 82.8 feet.
A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S1", attached at ground level, bears N19° 30' W, 84.1 feet.
A fence corner, with wire fences projecting N10° W and S45° W, bears N33° W, 42.5 feet. I nail a "Witness Post" sign to the wooden post at this fence corner.
I hereby certify the above corner point was perpetuated as hereon described on December 4, 2003. Magnetic declination set in compass: 19° E.
NAD '83 UTM Zone 11 position: 5059954N, 344537E (plus or minus two meters)

RECEIVED BY
Umatilla County Surveyor
Date 2-04
Rec'd By KK
No. 04-30-R

Renews June 30, 2005



Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on: