

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 03/15/06

CORNER DESIGNATION: 2N31, E-9, The Northeast Corner of Section 8.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Josiah A. Burnett, under Contract No. 92, dated September 12, 1860. Record states: Set a post for corner to Secs. 4, 5, 8 and 9, drove charred stake and raised mound of stone.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T2N R31E
S5 | S4
S8 | S9
2006
PLS 1106

MONUMENT SET:

Reestablished corner position by record proportioned departure between the reestablished Northwest Corner of Section 8 and the North One-Quarter corner of Section 9. For latitude at the corner point, I held remains of old wire and scattered old fence posts found East and West of the corner point. There is also a ancient fence, extending East, located several hundred feet East of the corner point. At reestablished corner position, set a 5/8" x 24" iron rebar with 2" aluminum cap with top 8" above ground level and surrounded with a mound of stone. Rebar was driven to bedrock. Cap marked as shown in monument marking detail.

From which:

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap stamped "OPLS 1106 WAPLS 17372", 12" above ground level at a large immovable rock bears North 34° East, 31.5 feet. Attached witness sign to rebar.

A railroad spike stamped "PLS 1106" with punch mark located in a rock outcrop bears North 87° East, 21.0 feet.

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap stamped "OPLS 1106 WAPLS 17372", 8" above ground level bears South 19° West, 22.0 feet.

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap stamped "OPLS 1106 WAPLS 17372", 6" above ground level bears North 73 1/2° West, 34.8 feet.

Attached bearing object signs to rebar accessories. Did not attach bearing object sign to railroad spike accessory.

LOCATION AND COMMENTS: Corner is located on a steep rocky hillside sloping West, 75 feet +/- North of the bottom of a rocky gulch.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 735892.99
E = 8597381.88

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

/2N31E9

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will R. Wells
OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-08

06-462-C