OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 05/13/06

CORNER DESIGNATION: 2N31, G-13, The West One-Quarter Corner of Section 10.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner established by Josiah A. Burnett, under Contract No. 92, dated September 12, 1860. Record states: Set a post for 1/4 Sec. corner, and raised stone mound, as per instructions.

G. Kimbrell, in survey recorded in Book 1, Page 485, reestablished this corner and states: "set Stake for 1/4 Sec. Cor."

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T2N R31E

 $\frac{1}{4}$

S9 | S10 2006

PLS 1106

MONUMENT SET:

Found and accepted a Southwest side of a 8' diameter mound of stone with wood and wire remains as best remaining evidence of the original corner position. Old rock jack mounds of stone extend North and East from accepted corner position. At accepted corner position, set a 2 3/8" brass cap on 1 1/4" x 30" galvanized iron pipe 3" in the ground to bedrock and surround with mound of stone and earth with a 3 1/2 foot diameter base. Monument marked as shown in monument marking detail.

From which:

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears North 24 1/2° East, 34.3 feet.

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears South 88 1/2° East, 34.4 feet.

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked " OR PLS 1106 WA PLS 17372" bears South 67 $1/2^{\circ}$ West, 32.1 feet.

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears North 39 1/2° West, 24.9 feet.

Attached bearing object signs to iron rebar accessories. Wired witness sign to large rock 3 feet North of corner monument.

LOCATION AND COMMENTS: Corner is located on a rocky South sloping hillside. Corner can be seen from Barnhart Road.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 733405.32

E = 8602686.41

FIRM: William R. Wells, PLS

P.O. Box 1696

Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

/2N31G13

REGISTERED PROFESSIONAL LAND SURVEYOR

> OREGON JULY 22, 1977 WILLIAM R. WELLS

Will-R. Wells

1106 renews 6-30-08

101.41.70