

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 01/24/06

CORNER DESIGNATION: 2N31, N-13, The Southwest Corner of Section 15.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner established by Josiah A. Burnett, under Contract No. 92, dated September 12, 1860. Record states: Set a post for corner to Secs. 15, 16 21 and 22, drove charred stake and raised mound with trench, as per instructions.

A marked stone with fences South and East, and a State Plane coordinate is noted on BPA Pendleton-McNary Transmission Line Survey maps dated 1950. Maps were found in County Assessors Office.

MONUMENT AND ACCESSORIES FOUND:

Found and held a 17"x8"x7" set stone in mound of stone with fence wire remains tied to rocks in mound. Could not identify any definite marks on the stone.

MONUMENT MARKING DETAIL:

T2N R31E
S16|S15
S21|S22
2006
PLS 1106

MONUMENT SET:

At position of set stone, set a 1 1/4" x 30" galvanized iron pipe with a 2 3/8" brass cap, 28" in the ground and raised a mound of earth and stone to the top of the cap. Set corner stone 1 foot Southeast of monument in mound of earth. Monument marked as shown in Monument Marking Detail.

From which:

A 5/8" x 30" iron rebar with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", bears North 54 1/2° East, 27.7 feet.

A 5/8" x 30" iron rebar with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", bears South 10 1/2° East, 35.6 feet.

A 5/8" x 30" iron rebar in fence line with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", bears South 75 1/2° West, 41.5 feet.

A 5/8" x 30" iron rebar with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", bears North 21° West, 41.2 feet.

Attached bearing object signs to all rebar accessories. Set steel fence post with witness sign attached 2 feet East of monument.

LOCATION AND COMMENTS:

Corner is located on East facing hillside approximately 100 feet East of a range fence.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 725463.93
E = 8602862.05

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

/2N31N13



renews 6-30-08 06-462-C