

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 01/23/06

CORNER DESIGNATION: 2N31, P-21, The East One-Quarter Corner of Section 23.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner established by Josiah A. Burnett, under Contract No. 92, dated September 12, 1860. Record states: Set a post for 1/4 Sec. corner, drove charred stake and raised mound with trench, as per instructions. Corner was reestablished in Record of Private Surveys, Book 1, Page 484, by John Kimbrell in 1902. Kimbrell's record states "Set stone 22 x 5 x 10 for 1/4 Sec. Cor." Corner was recovered and noted as a 5" x 6" x 20" stone marked "1/4" on west face on Survey No. D-39-B

MONUMENT AND ACCESSORIES FOUND:

Found 37"x10"x7" stone set firmly in ground with top 12" above ground level marked 1/4 on west face. Stone is 6 feet North of and 8 feet East of a fence corner with fences North, South, East, and West.

MONUMENT MARKING DETAIL:

T2N R31E
1/4
S23|S24
2006
PLS 1106

MONUMENT SET:

At the position of the found set stone set a 1 1/4" x 30" galvanized iron pipe with 2 3/8" brass cap with top 6" above ground level. Placed original corner stone with marks facing up 1.5 feet South of brass cap monument and raised mound of earth to top of cap. Stamped cap as shown in monument marking detail.

A 5/8" x 24" iron rebar with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", bears North 05 1/2° West, 54.8 feet.

A 5/8" x 24" iron rebar with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", bears South 83° East, 68.1 feet.

A 5/8" x 24" iron rebar with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", bears South 72° East, 28.4 feet.

A 5/8" x 24" iron rebar with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", bears South 14° West, 38.3 feet.

Attached bearing object signs to all rebar accessories and nailed witness sign to fence corner 8 feet West of monument.

LOCATION AND COMMENTS:

Corner is located 6 feet North of and 8 feet East of a fence corner with fences North, South, East, and West.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 723001.29
E = 8613422.41

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT

/2N31P21

Surveyor's Seal



William R. Wells
OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-08 06-462-C