

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


T 2N, R 32E., W.M.

Corner Code No. P-1

Note: Monument marked as shown below

History of original corner establishment:

Corner was originally set by Josiah A. Burnett, under Contract No. 98, dated September 12, 1889. At which time he set a charred stake, and raised a mound and trench, for the 1/4 corner to S24 1/2N R31E and S19 1/2N R32E.



In 1950, Bonneville Power Administration noted an old fence intersection as the 1/4 corner on their Transmission Line Maps.

Corner No. Compass Declination: 18.0°

Description of corner evidence found:

Found an old fence corner and a 1/2" iron pin (origin of pin is unknown). Existing fences run North and West.

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2 1/2" brass cap on a 1 1/4" by 30" galv. iron pipe, 30" in ground, and surrounded with a mound of earth. New monument was set at the position of the 1/2" iron pin. Buried the 1/2" iron pin in new mound. Set a steel fence post 2' West of the corner with a Witness corner sign attached.

New bearing objects:
A 5/8" x 30" iron pin bears N 0 1/2° W - 19.7 feet.
A 5/8" x 30" iron pin bears N 71° E - 26.3 feet. (Buried 14" below ground).
A 5/8" x 30" iron pin bears S 57 1/2° E - 30.3 feet. (Buried 12" below ground).
A 5/8" x 30" iron pin bears N 85° W - 24.1 feet.

All pins are capped with a 1 1/2" yellow plastic cap marked "W.R.WELLS, PLS 1106". Bearing Object signs are wired to each pin.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

expires 12/31/94

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by (DEPUTY)
(COUNTY OFFICIAL)

93-54-C
an asur