

**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**


T 2N, R 32E., W.M.

Corner Code No. V-1

Note: Monument marked as shown below

**History of original corner establishment:**

This corner was originally established by Josiah A. Burnett, Deputy Surveyor, under Contract No. 92, dated September 12, 1860. Set post, drove charred stake, and raised mound with trench, as per instructions.



Corner No.  
Compass Declination: 18.0°

**Description of corner evidence found:**

Found ancient fence corner with fences extending North and West. The position of this fence corner was verified by survey between known corners to the North and South. The fence corner was accepted as the best remaining evidence of the corner location.

**Description of monument and accessories established to perpetuate the original location of this corner:**

Set: A 2 1/2" brass cap on 1 1/4" x 30" galv. iron pipe, 29 inches in the ground, 0.2 feet Southeast of the railroad tie fence corner.  
Attached a Witness corner sign to the railroad tie fence corner post.

**New Bearing Objects:**

- A 5/8" x 30" iron pin bears N 03° E - 19.8 feet.
- A 5/8" x 30" iron pin bears N 53° E - 15.7 feet.
- A 5/8" x 30" iron pin bears S 30° E - 21.3 feet.
- A 5/8" x 30" iron pin bears S 89 1/2° W - 18.5 feet.

All iron pins are capped with a 1 1/2" yellow plastic cap, marked: "WR WELLS, PLS 1106". Bearing Object signs are wired to each iron pin.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*expires 12/31/94*

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by .....

(COUNTY OFFICIAL)

(DEPUTY)