

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 2N, R 32E., W.M.

Corner Code No. A-17


Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by D. Thompson, U.S. Deputy Surveyor, under Contract No. 106, dated August 16, 1864. The original notes state that at the corner a wood post, with charred stake, earth mound and pits was set for the corner.

Record of Private Surveys, Book 1, located in the County Surveyor's Office, at Page 318, shows a statement by John Kimbrell, that he made surveys and set of recovered corners for Section 2 and Section 1 as shown on Page 310. Page 310 shows a measurement of 80.09 chains across the north line of Section 2, so apparently Kimbrell had recovered this corner prior to 1895.

This corner position was reestablished by Terry Hamby, as part of a survey shown on Map No. R-23-B.



Corner No.
Compass Declination: 18.0

Description of corner evidence found:

Found 3" brass cap on a 2 1/2" galv. iron pipe protruding 10" from the ground at the east edge of a wheat field.

Description of monument and accessories established to perpetuate the original location of this corner:

This corner monument could not be mounded because it is in a wheat field. Measurements were made to reference objects as follows. From the existing monument:

An aluminum nail in the south side of Pole No. 350061 bears N44°E 74.32'. The nail is about 1' above the ground. Attached witness corner and bearing object signs to the pole.

An aluminum nail in the N.W. corner of a railroad tie in a fence corner bears S83°E 54.47'. The nail is 1' above the ground. Attached witness corner and bearing object signs to the railroad tie.

An aluminum nail in the S.W. corner of a railroad tie near the corner monument bears S35°E 1.83'. The nail is about 4" above the ground. Attached witness corner and bearing object sign to the railroad tie.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19....

..... by
(COUNTY OFFICIAL) (DEPUTY)