

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 2N, R 32E., W.M.

Corner Code No. C-25

Note: Monument marked as shown below

History of original corner establishment:

Contract No. 106, in 1864, states that a 15" by 10" by 4" stone was set for the corner.


Contract No. 145, in 1871, superseded Contract No. 106, and states that a wood post and mound was set for the corner.

Special Instructions and Contract dated 1887, show that the corner was recovered and re-monumented with a 9" by 8" by 7" stone.

In 1917, L.E. Wilkes, under Group 29 Instructions, did a resurvey of the diminished Umatilla Indian Reservation boundary and reestablished the corner after declaring it lost as follows: "Set an iron post, 3 ft. long, 2 ins. diam., 24 ins. in the ground, for 1/4 cor. of sec. 1, T. 2 N., R. 32E. only, with barked brass cap".

Map G-1297-A, done by W.E.O. Criger in 1948, shows a tie to the corner but corner monument composition was not identified.

The Plat of Mt. Hebron also show a tie to this corner.



Corner No.
Compass Declination: 18.0

Description of corner evidence found:

Found a 1/2" square rod, 24" long. The top of this rod was 15" below the top of a wheat field near the east edge of the field. The monument found is believed to be a perpetuation of the corner location as determined by L.E. Wilkes in 1917, because the distance between the found 1/2" iron rod and the N.W. corner of the Diminished Indian Reservation is within 1/2' of matching the original survey record.

Description of monument and accessories established to perpetuate the original location of this corner:

At the found corner position I set a 2 1/2" brass cap on a 1 1/2" by 30" galv. iron pipe, with the cap 19" below the ground surface. Referenced the monument as follows. From the new corner monument:

A 1 1/2" yellow plastic cap marked "W.R. Wells PLS 1106", set on a 5/8" by 30" iron rod bears S28 1/2°E 17.27'. Set steel fence post near reference monument and attached witness corner and bearing object sign.

A 1 1/2" aluminum cap, marked as shown, set on a 5/8" by 30" iron rod bears N21 1/2°E 25.47'. Set steel fence post near reference monument and attached witness corner and bearing object sign.

The reference monuments are set near the east edge of the wheat field.

The aluminum cap on the reference monument is marked as follows:

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106



Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)