

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 2N , R 32E. , W.M.

Corner Code No. E-1


Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by J. Burnett, U.S. Deputy Surveyor, under Contract No. 92, dated September 12, 1860. The original notes state that at the corner a wood post was set with charred stake, earth mound and pits.

In 1902, this corner was recovered and used by Surveyor John Kimbrell in County Survey No. 147.

In 1904, the corner was recovered and used by Surveyor John Kimbrell in County Survey No. 212.



Corner No. Compass Declination: 18.0

Description of corner evidence found:

None. This corner was reestablished by single proportion measure between the reestablished S 1/16 corner common to Sections 7 and 12 and the reestablished N.W. corner of Section 6, using John Kimbrell's record distances from County Surveys No. 147 and 212.

Description of monument and accessories established to perpetuate the original location of this corner:

The corner point falls in a wheat field, 19' South of a east-west fence. At a point North 0°13'07" East 19.00 feet from the true corner point I set a witness corner monument. The witness corner monument is a 2 1/2" brass cap on a 1 1/2" by 30" galv. iron pipe set 24" in the ground and surrounded with a mound of earth and stone. Set two reference monuments referencing the witness corner point. From the witness corner monument:

A 1 1/2" yellow plastic cap marked "W.R. Wells, PLS 1106", set on a 5/8" by 30" iron rod bears N89°W 25.99'.

A 1 1/2" alum. cap marked as shown, set on a 5/8" by 30" iron rod bears S89°E 19.56'.

Both reference monuments are near the east-west fence.


Set steel fence post west of the witness corner monument with witness corner sign attached. Set steel fence post with witness corner sign and bearing object sign attached near each reference monument.

The aluminum cap on the reference monument is marked as follows:

REGISTERED PROFESSIONAL LAND SURVEYOR

William R. Wells

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106



Office of..... County of..... State of..... I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by ..... (COUNTY OFFICIAL) (DEPUTY)