

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 2N, R 32E., W.M.

Corner Code No. E-23

Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by D. Chaplin, U.S. Deputy Surveyor, under Contract No. 107, dated August 21, 1864. The original notes state that at the corner a 16 by 12 by 4 stone was set for the corner from which a 15" balm bears S10°E 290 lks.


In 1871, Z.F. Moody, during his survey of Contract No. 164, reestablished the corner by setting a 20 by 14 by 7 inch stone.

In 1887, Currin and Noland, under their Special Instructions and Contract, reestablished the corner and set a 18 by 10 by 8 inch stone from which a 4" balm bears N72°W 19 lks marked 1/4 S Bl. A 6" balm bears S70°W 70 lks marked 1/4 S Bl.

In 1895, during County Survey No. 75, John Kiebrell recovered the corner, but does not state what type of monument was found.

The Plat of Lassen Subdivision, recorded in 1920 and surveyed by Aubrey E. Perry, shows a "rock" existing for the 1/4 corner.

This corner was last reestablished by Wayne Harris in 1978, see Map No. Q-1121-B.



Corner No.
Compass Declination: 18.0

Description of corner evidence found:

Found P.K. nail in a concrete slab as established by Wayne Harris in 1978, see Map No. Q-1121-B. From the p.k. nail, a 1/2" iron rod bears S22°W 1.74'.

Description of monument and accessories established to perpetuate the original location of this corner:

A found p.k. nail, set a 3" brass disc in mortar in the concrete slab.

New references are as follows. From the new corner monument:

The existing 1/2" iron rod bears S22°W 1.74'.

A P.K. nail in the center of a 1 1/2' concrete walk on the east side of a paved road bears N86°E 63.00'.

The new corner monument is located 1.00' north of the south edge and 19.1' west of the east edge of the concrete pad.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)