

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 2N, R 32E., W.M.

Corner Code No. E-9


Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by D. Chaplin, U.S. Deputy Surveyor, under Contract No. 107, dated August 21, 1884. The original notes state that at the corner a 24" by 12" by 10" marked basalt stone was set for the corner.

The next recorded reference to the corner appears in 1950 when the corner was used by W.E.O. Criger to reestablish the South 1/4 corner of Section 5.

This corner was reestablished by Stanley G. Wallulis in the 1961. I find no record of reestablishment in county records. A City of Pendleton corner card indicates that the corner was reestablished and monumented by Stanley Wallulis in 1961.



Corner No.
Compass Declination: 18.0

Description of corner evidence found:

Found 1/2" square iron rod protruding 1/2" from an 18" circular block of concrete. The concrete around the 1/2" iron rod is etched as shown in the corner diagram. The top of the concrete is level with the top of gravel in the parking area where the corner is found.

Note: The year of the date etched on the concrete could not be read.

Description of monument and accessories I established to perpetuate the original location of this corner:

Established references to the existing corner monument as follows. From the existing corner monument:

An aluminum nail in the west side of the west pole support for the Historical Marker Sign bears S34° E 51.65'. The nail is about 1' above the ground. Attached bearing object sign to the south side of the support pole.

A 1 1/2" aluminum cap, marked as shown, set on a 5/8" by 30" iron rod bears S34° W 65.23'. Set steel fence post near the reference monument and attached witness corner and bearing object sign.

The aluminum cap on the reference monument is marked as follows:

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106



Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)