

PUBLIC LAND CORNER CONDITION REPORT

UMATILLA COUNTY, DATE: 02/04/02

CORNER DESIGNATION: 2N32G5, The East Quarter corner of Section 7.

PREVIOUS RENEWALS/ SURVEYS, ETC..:

Most recent Umatilla County Surveyors Corner Record: 90-50-C.

MONUMENT AND ACCESSORIES FOUND:

Found a 2 1/2" brass cap on galvanized iron pipe monument, with cap flush with ground in small mound of stone, marked as shown in monument marking detail.

N21°E bearing tree is now a 12" hawthorn with visible scribes. S 69° W bearing tree is gone. Willow bearing tree bearing S 37° W bearing tree is uprooted and on the ground. Willow bearing tree bearing S 20° E is standing but dead. Lots of dead and down trees in area and evidence of beavers cutting trees.

MONUMENT MARKING DETAIL:

T2N R32E
1/4
S7 | S8
1990
PLS 1106

LOCATION & COMMENTS:

Corner located in fallen down North-South fence approximately 150 feet South of South edge of Umatilla River.

STATE PLANE COORDINATE, OREGON NORTH ZONE, NAD83/91, INT. FOOT:

N = 733642.97
E = 8624217.45

FIRM/AGENCY: William R. Wells
P.O. Box 1696
Pendleton, Oregon 97801

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will. R. Wells

OREGON
JULY 22, 1976
WILLIAM R. WELLS
1106

renews 6-30-02

2N32G5

Karen A. Neuman

05
26
05

RECEIVED BY

Umatilla County Surveyor

Date 2-02

Rec'd by JK

No. 02-43-9