

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


T 2N , R 32E . , W.M.

Corner Code No. H-1

Note: Monument marked as shown below

History of original corner establishment:

This corner point was apparently in existing when the Plat of the Town of Doris was surveyed and recorded in 1916. The Plat of the Town of Doris, surveyed by Peary Kimbrell, shows a bearing and distance tie from the initial point of the plat to the South 1/16 common to Sections 7 and 12.



Corner No.
Compass Declination: 18.0

Description of corner evidence found:

None. The reestablished corner point falls 5 feet South and 16 feet west of a fence corner with a crooked fence running east-west and south.

Description of monument and accessories I established to perpetuate the original location of this corner:

At the corner position determined by computation from the existing 2 1/2" brass cap monuments located at the intersections of Main and Bollons Streets and Main and Morrow Streets in the Town of Rieth (formerly Doris), I set a 2 1/2" brass cap on 1 1/2" by 30" galv. iron pipe, 18" in the ground to bedrock and surrounded with a mound of earth and stone. From the reestablished corner monument, set two reference monuments:
A 1 1/2" yellow plastic cap marked "W.R. Wells, PLS 1106", set on a 5/8" by 30" iron rod bears N61° W 10.91'.
A 1 1/2" alum. cap marked as shown, set on a 5/8" by 30" iron rod bears N52° E 6.81'.

Set steel fence post north of corner and attached witness corner sign.
Set steel fence posts near each reference monument and attached bearing object sign and witness corner sign.


The corner bears N18° 21' 12" W a distance of 770.76' from the 2 1/2" brass cap monumenting the intersection of centerlines of Main and Bollons Street in the Town of Rieth.

The aluminum cap on the reference monument is marked as follows:

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106



Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19....
..... by
(COUNTY OFFICIAL) (DEPUTY)