

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 2N, R 32E., W.M.

Corner Code No. J-15

Note: Monument marked as shown below

History of original corner establishment:


Corner was originally established by Daniel Chaglin, U.S. Deputy Surveyor, under Contract No. 107, dated September 21, 1864.

Z.F. Moody, U.S. Deputy Surveyor, in Contract No. 164, dated October 4, 1871, established a new corner. This new corner superceded that corner established under Contract No. 107.

Currin and Noland, U.S. Deputy Surveyors, under Special Contract dated May 4, 1887, unable to find Moody's corner, re-established it based on Moody's survey.

Several surveys in Record of Private Surveys, Books 1 and 2, indicate recovery of this corner.

All recent surveys report recovery and use of a iron rod or hex rod at this corner.



Corner No. Compass Declination: 18.0

Description of corner evidence found:

Found 1" by 12" hexagon rod, set flush with ground, at fence corner with fences running West and South.

Also found 15" by 10" by 9" basalt stone, with a faint "X" chiseled on it, in small stone mound 25' north of the hexagon rod.

Description of monument and accessories established to perpetuate the original location of this corner:

At the position of the found hexagon rod, set a 2 1/2" brass cap on a 1 1/4" by 30" galvanized iron pipe 20" in the ground to bedrock and surrounded with a mound of earth and stone. Buried the hexagon rod in the new stone mound.

From the remonumented corner point:

An "X" chiseled on the South face of a 6' by 5' by 1' out of the ground rock outcrop bears N 17°E 48.84'.

An "X" chiseled on the West side of a large rock rim, or outcrop, bears N 81°E 99.62'. The "X" is 18" above ground.

The base of the 1st steel fence post South of the corner monument bears South 19.40'. Attached bearing object sign to this steel fence post.

The Northwest corner of the Pendleton Tennis Center Tract, a 5/8" by 30" iron pin with 1 1/2" yellow plastic cap marked "W.R.Wells PLS 1106", bears S80°04'30"W 772.78'.

Set steel fence post 3' West of corner monument with witness corner sign attached.

REGISTERED PROFESSIONAL LAND SURVEYOR

William R. Wells

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

Office of Survey Dept. County of Umatilla State of OR I hereby certify that the within instrument was filed in this office for record on the day of July 19 1970 David H. Lumbard by Kathleen K. Amberg (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY Umatilla County Surveyor *GPO: 1989-692-049 Date 7-90 No. 9A-5A-1