

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


T 2N, R 32E., W.M.

Corner Code No. J-17

Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by Daniel Chaplin, U.S. Deputy Surveyor, under Contract No. 107, dated September 21, 1864.
 Z.F. Moody, U.S. Deputy Surveyor, in Contract No. 164, dated October 4, 1871, established a new corner. The Moody corner superseded the corner established by Daniel Chaplin.
 Currin and Noland, U.S. Deputy Surveyors, under Special Contract dated May 4, 1887, recovered Moody's corner and re-monumented it.
 There are several references to recovery and use of this corner in Record of Private Surveys, Books 1 and 2.
 In 1968, as shown on Map No. E-29-B, LS 346 determined the best remaining evidence of the corner was the existing fence lines. The corner was re-monumented with a brass capped iron pipe.
 Since 1968, this re-monumented corner has been used on all area surveys.



Corner No.
Compass Declination: 18.0

Description of corner evidence found:

Found 2 1/2" brass cap on a 1 1/4" galvanized iron pipe, marked as shown in corner diagram. The top of the brass cap is 4" below ground.
 The brass cap monument is located 0.5' South of a East-West board fence.

Description of monument and accessories established to perpetuate the original location of this corner:

Maintained corner by placing a witness corner sign on the exist. metal fence post 1' Northwest of corner monument.
 Referenced the corner monument as follows:
 Centerline of the most Southerly phone pedestal in a group of 2 bears West 94.9'.
 A brass washer nailed to the West side of PP&L Pole No. 140900, 3' above ground, bears S 3°E 61.4'.
 The centerline of a round metal fence post at the Northwest corner of a chain link fence bears S 87 1/2°E 36.0'.
 A brass washer in the South side of PP&L Pole No. 110000, 3' above ground bears East 26.7'.
 The brass washers are stamped "PLS 1106". Attached bearing object signs to the two power poles.

REGISTERED PROFESSIONAL LAND SURVEYOR
<i>William R. Wells</i>
OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

Office of Survey Dept. County of Umatilla
 State of OR I hereby certify that the within instrument was filed in this office
 for record on the 10 day of July, 1980
David H. Lusk by William R. Wells
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY
 UNIT 2-90
 REC'D BY HA
 No. 90-50-C