

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 2N, R 32E., W.M.

Corner Code No. J-21

Note: Monument marked as shown below

History of original corner establishment:


This corner was originally established by Daniel Chaplin, U.S. Deputy Surveyor, under Contract No. 107, dated September 21, 1864.

Z.F. Moody, U.S. Deputy Surveyor, in Contract No. 164, dated October 4, 1871, established a new corner. The Moody corner supercedes the corner by Chaplin.

Currin and Noland, U.S. Deputy Surveyors, under Special Contract dated May 4, 1887, recovered Moody's corner and re-monumented it.

In 1968, as shown on Map No. E-29-B, LS 346 determined the best remaining evidence for the corner was an existing fence corner and re-monumented with a brass capped iron pipe.

All surveys in the area, since 1968, have used this monument.



Corner No.  
Compass Declination: 18.0

Description of corner evidence found:

Found a 2 1/2" brass cap on a 1 1/4" galvanized iron pipe, protruding 2" from the ground. Fences go North-South and West from the corner. The cap is marked as shown in the corner diagram.

Description of monument and accessories established to perpetuate the original location of this corner:

Referenced corner monument as follows:

Set steel fence post 1' North of corner with witness corner sign attached.

A brass washer nailed to the West side of PP&L Pole No. 119001, 3' above ground bears N 6° W 33.1'.

A brass washer nailed to the West side of PP&L Pole No. 119002, 3' above ground bears N 14° W 12.0'.

A brass washer nailed to the North side of a power guy pole, 3' above ground bears West 20.1'.

A brass washer nailed to the East side of a cut off power pole in fence line, 2' above ground, bears S 6° W 8.3'.

Attached bearing object signs to each of the poles.

Brass washer are marked "PLS 1106".

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

Office of Survey Dept County of Umatilla

State of OR, I hereby certify that the within instrument was filed in this office

for record on the 14th day of July, 1978

David A. Thurmond by William R. Wells  
(COUNTY OFFICIAL) (DEPUTY)

Umatilla County Survey Dept  
RECORDED 7-90  
INDEXED AT