

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 2N, R 32E., W.M.


Corner Code No. J-25

Note: Monument marked as shown below

History of original corner establishment:

This corner had been established and re-established a number of times prior to 1917.

In 1917, L.E. Wilkes, under Group 29 Instructions, made a resurvey of the Diminished Umatilla Indian Reservation Boundary, re-established the corner and monumented it with a iron post, 3' long and 2" in diameter.



Corner No.
Compass Declination: 18.0

Description of corner evidence found:

Wilkes bent 1917 monument, a 2 1/2" brass cap on a 2" galvanized iron pipe. The top of the monument was 2' below ground on the East side of the cutbank of the County Road.

Description of monument and accessories I established to perpetuate the original location of this corner:

At the position of the base of the found monument, set a 2 1/2" brass cap on 1 1/4" by 30" galvanized iron pipe. The top of the new monument is 12" below ground. Buried Wilkes monument alongside new monument. Set steel fence post 1' North of corner and attached witness corner sign.

Reference new corner monument as follows:

The Northwest corner of Section 18 bears N 00°06'35" W 258.44'. The base of a metal brace post on the fenceline on the East side of the County Road bears N 2°E 61.1'. Attached bearing object sign to the brace post.
A brass washer stamped "PLS 1106" nailed to the East side of a road sign post, 6" above ground, bears N 6°W 46.10'. Attached bearing object sign to the signpost.
A brass washer stamped "PLS 1106" nailed to the North side of a railroad tie fence post, 4" above ground bears S 63°W 63.09'. Attached bearing object sign to the post.

The corner is 1' West of a fence along the East side of the County Road.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of Survey Dept. County of Umatilla
State of OR I hereby certify that the within instrument was filed in this office
for record on the 19 day of July 1990
David H. Kumbrow by Kathleen K. Amberg
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Umatilla County Surveyor
Date: 7-90
Rec'd by: KA
No. 90-50-C