


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

L-1

History of original corner establishment:

Corner originally ESTABLISHED by Josiah A. Burnett under GLO Contract No. 92 dated September 12, 1860, and his record states:
"Set a post for 1/4 sec. cor. drove charred stake and raised mound as per instructions."



Corner REESTABLISHED by Willard Bradley, County Surveyor, on April 22, 1916, as recorded in Book 2 at Pages 284 thru 287 in the Record of Permanent Surveys of the Umatilla County survey records. At position determined by single proportionate measurement between recovered adjacent section corners north and south his record states:
"Set 1/4 corner stone 20"x7"x7" marked 1/4 on south and raised mound of stone."

Description of corner evidence found:

Found a basalt stone 20"x7"x7" marked 1/4 on southeast face firmly set in the middle of a surrounding rock mound 3-feet in diameter. The recovered stone and rock mound have been in place and undisturbed for a very long time as evidenced by lichen covered stones which are nearly flush with the surrounding ground surface.

Description of monument and accessories established to perpetuate the original location of this corner:

I removed the recovered corner stone and set a 1-inch dia. galvanized iron pipe 30-inches long with a 2 1/2-inch dia. brass cap attached to bedrock at a depth of 18 inches in its place. The recovered surrounding rock mound was not disturbed, however, additional stones were added to the base of the brass cap. The original corner stone was placed on the southwest side of the improved surrounding rock mound with the marked face down. I placed a 6-foot long steel fence post on east side of the rock mound, 3 feet distance, with a Umatilla County survey monument attention sign attached. Brass cap is marked as shown in corner diagram.

There being no trees or suitable bearing objects available, I set the following described referenced monuments.

A 5/8"x30" rebar brs. N 15°30' E, 20.0 feet distance with a 1 1/2-inch dia. aluminum cap attached and marked thus:



A 5/8"x30" rebar brs. N 70°30' W, 9.1 feet distance with a 1 1/2-inch dia. aluminum cap attached and marked thus:



Each rebar reference monument has a 6-foot long fence post placed alongside with a Umatilla County survey monument attention sign and bearing object information sign attached.

I hereby certify that the above described corner was properly remonumented by me on May 21, 1989.

Office of..... Survey Dept County of..... Umatilla
State of..... OR I hereby certify that the within instrument was filed in this office
for record on the..... 25 day of..... May..... 1989
David H. Krambert by..... Kathleen J. Amberg
(COUNTY OFFICIAL) (DEPUTY)

REGISTERED PROFESSIONAL LAND SURVEYOR
William L. Hanley
OREGON
JULY 14, 1978
WILLIAM L. HANLEY
1639

RECEIVED BY

Umatilla County Surveyor
Date 5-89
Rec'd By [Signature]